LUNAR CORE DRILL

Ьу

Matthew Adams James Broom Barry French Mark Hajos Otto Monnig Nancy Shaler

(NASA-CR-183270) LUNAR CORF DRILL (Georgia Inst. of Tech.) 84 p

N91-10239

Unclas 03/37 027985

for

ME 4182

June 3, 1985

CONTROL DEPARTMENT OF MECHANICAL ENGINEERING

GEORGIA INSTITUTE OF TECHNOLOGY

ERCCP 4

## TABLE OF CONTENTS

Abstract1
Problem Statement2
Detailed Description5
Arm Design5
Drill String Assembly8
Footplate Assembly8
Pumping System for Cooling and Chip Removal.9
Controls10
Cost Analysis11
Hazards and Failure Modes
Operating Instructions
Recommendations and Conclusions20
Appendix
Calculations/Computer Usage
Drawings
Operating Positions of the Arm
Alternative Designs
Bibliography

Acknowledgements

Record of Invention

#### **ABSTRACT**

This report presents a unique design of a core drilling mechanism which could be used on the moon to collect rock cores to depths of 100 feet below the surface. The design is necessarily unique due to the fact that the moon has virtually no atmosphere and only one-sixth the gravity of earth. These adverse conditions require certain important concepts to be included in the design. The most notable of these concepts are:

- The complete use of hydraulic power to operate the device;
- The use of Teflon beads to cool the bit and remove the chips;
- 3. The use of extensive automation to reduce the dexterity requirements of the astronauts.

In addition, the actual drilling force will be transmitted by a robot arm that functions much like a backhoe. Thus, with a bucket or digging attachment it would be possible to use the arm in two ways: either as a core drilling mechanism or as a lunar excavator. The major topics discussed in this report include the following:

- 1. Arm design;
- 2. Drill motor, drill string, core barrel and bit, core retriever, and footplate:
- 3. Pumping system for cooling and chip removal:
- 4. Hydraulic power system and electrical controls.

#### PROBLEM STATEMENT


Basic Statement: The problem is to design a core drill for use on the moon which can be operated by astronauts efficiently and will reliably obtain intact core samples from depths of 100 feet. Ideally, the core drill is to be capable of pivoting 180 degrees in a horizontal plane and coring a hole at any angle within the range of -90. to 90. degrees woth respect to vertical.

Backround: Core drilling is frequently done on earth to aid in evaluating the underground geological properties of sites being considered for construction or mining purposes. Analyzation of the core can provide the geologist with much important information concerning the formation of the underground rock, the strength, and the compostion—all fo which aides the engineer in deciding how best of use a particular site. Thus, core drilling is common, and, having been practiced for many years, is technologically sound on earth.

However, it is not feasible to handle core drilling on the moon in exactly the same manner as it is handled on earth. The fact that the moon has virtulally no atmosphere and only one-sixth the gravity of earth gives rise to two basic difficulties concerning lunar core drilling which are unaccounted for in earth core drilling technology. These two basic difficulties are as follows:

- 1. Lubrication: Water or mud is used as a lubricant and chip remover for core drills on earth. However, because the moon has no atmosphere, water evaporates rapidly and thus cannot be used as a lubricant. A nonvaporizing lubricant, possibly solid Teflon beads, is necassary in a lunar design.
- 2. Automation: On earth, much of the work involved in core drilling requires an average amount of manual labor and physical dexterity. On the moon, however, the physical dexterity of astronauts is limited due to the bulky space suits and the low level of lunar gravity. Thus, a lunar core drill needs to be highly automated in order to be operated efficiently by the "handicapped" astronauts.

One other major difficulty concerns the range of motion required for this particular lunar core drill design. Core drills on earth are not made to function similar to backhoes and are not mormally designed to meet the angular requirements



of this particular lunar design. Therefore, the decision to design the drilling mechanism similar to a backhoe linkage represents a step into delicate and untested technology.

Aside for the three major difficulties discussed above, the lunar core drill will be able to function in much the same was as an earth core drill. An abundance of information is available on the subject of earth core drilling and several large companies produce core drilling equipment which they offer commercially. Many of these commercially available assemblies, such as the drill motor, drill string, drill bit, core barrel, core retrieval mechanism, and breakout tool can be used effectively in a lunar design without difficult modifications.

Performance Objectives and Constraints: The following performance objectives and constraints for the core drilling mechanism served as guidelines during the design process. Many of the objectives and constraints remained unchanged throughout the course of the design period; however, slight modifications were made, and these modifications are noted below in parentheses.

#### A. Transmission of Drilling Force:

- 1. Transmission device to be a robotic arm, similar to a backhoe;
- 2. Arm to have a 5' to 6' linear stroke;
- 3. Arm to be capable of linear stroke at angles ranging from -90. to 90. with respect to vertical. (objective later changed to include only angles form -45. to 45. with respect to vertical;
- 4. Base of main arm to be connected to tractor by way of a single pivot which is to rotate 180. in a horizontal plane;
- 5. Arm to be hydraulically operated;
- 6. Maximum force transmitted to be  $\geq$  8000 lbf in hole.

#### B. Drill Motor:

- 1. Motor to be hydraulically operated and reversible;
- 2. Motor to be variable speed, capable of 1200 rpm.

#### C. Drill String:

- 1. Total string to read 100 feet;
- 2. String to accept wireline overshot for core retrieval.

#### D. Core Barrel and Bit:

- 1. Barrel to hold 5' core;
- Core barrel keep core separated from lubrication fluid in hole:
- Core barrel to accept wireline overshot for core retrieval;
- 4. Diamond drill bit to be capable of cutting continuously through at least 100 ft of very hard basalt.

The sale of the sale of

#### E. Core Retriever:

- 1. Wireline overshot to be retractable:
- 2. Wireline overshot to be of such a design that it can be forced down hole if necessary;
- 3. Wireline overshot to retrieve 5' core intact;
- 4. Winch to be used in raising and lowering overshot;
- 5. Winch to be hydraulically powered.

#### F. Foot Plate:

- 1. Foot plate to clamp and hold string in hole while new string secton is readied for assembly.
- Foot plate to be used as a "break out" tool when necessary;
- 3. Foot plate to be capable of making angles ranging from -90. to 90. with respect to vertical. (Objective later changed to include only angles from -45. to 45. with respect to vertical.)

#### 6. Lubrication and Pumping System:

- 1. Lubricant to be nonvolitale in absence of atmosphere:
- Lubricant to be capable of both cooling drill bit and removing chips;
- 3. Lubricant to be separated from chips;
- 4. Lubricant to be reused continuously in closed loop;
- 5. Pump to be hydraulically powered.

#### H. Hydraulic Power System and Electrical Controls:

- Hydraulic system to operate at or below 2500 psi and 25 gpm;
- Electrical controls to operate at or below 24 VDC and 70 amps;
- 3. Control valves to precisely regulate hydraulic fluid flow to linear actuators on robot arm.

#### DETAILED DESCRIPTION

Arm Design: Determining a kinematically feasible configuration for the robot arm was a difficult task. Several different designs were evaluated before a satisfactory solution In order to make the arm functional, it was necessary to reduce its angular range of motion. design, then, consists of a 3-bar, hydraulically operated backhoe type arm which is capable of swinging 180. in a horizontal plane, but, compromisingly, can produce a six foot linear stroke at <u>reduced</u> angles ranging only from -45. to 45. with respect to vertical. The maximum drilling force which can be exerted by the design is 8000 lbf.

The reduced angular range of the design reflects the modification made to an original performance objective which had required the mechanism to produce linear strokes at angles ranging from -90. to 90. The reduction in angular range, from -90. to 90. to -45. to 45., was made because of two important reasons:

1.) the commercially available break out tool selected for use in the design will not accommodate holes drilled at angles ranging form more that -45. to 45. with respect to vertical, and 2.) hydraulic cylinders with the required bore and stroke dimensions necessary for reliable use in a design which would satisfy the original angle performance objective are not commercially available.

Specific information concerning the final arm design is as follows:

Dimensions, Forces, Moments, and Angular Range of Final Arm Design (See drawings no. 101-121 in Appendix)

Effective link lengths of drilling mechanism:

Arm	Effective Link	Length
Boom arm		8 ft.
Middle arm		4 ft.
Drill arm		2 ft

Maximum Joint Moments created by the 8000 lbf drilling force and the required hydraulic forces necessary to balance such moments:

Joint	Max. Moments	Hyd. Bal. Force Req.
Boom joint	63,030 ft.lbf	64,700 lbf
Middle joint	6,874 ft.lbf	7,270 lbf
Drill joint	8,000 ft.lbf	2,110 lbf

Quantity, bore size, stroke length, and force capacties of hydraulic cylinders determined using a factor of safety of 1.5):

Cylinders\* Quantity Bore Size Stroke Length Total Force

	·-			-
Boom arm	2	5"	40"	98,000 lbf
Mid. arm	1	3"	40"	17,650 lbf
Drl. arm	1	2 "	20"	7,850 lbf

\*note: All cylinders are double-acting.

The robot arm will be capable of drilling a 45. hole inward (toward) the tractor at a distance of 3' from the base of the boom arm. It will be capable of drilling a 45. hole outward (away from) the tractor at a distance of 12 1/2' from the base of the boom arm. Other angles within the 90. range (45. inward, 45. outward) may be drilled at spots between 3' and 12 1/2' from the base.

## Auxiliary Arm (See Drawing no./00 in Appendix)

A separately controllable auxiliary arm is designed to work in conjunction with the main arm outlined above. The auxiliary arm's function is to aide in the automatic assembly and disassembly of string sections. The auxiliary arm is attached to the middle link of the main arm and is designed with a hydraulically operated clamp on its free end. During the assembly and disassembly of the drill string, the auxiliary arm will be used to carry each successive section to or from a core tube rack and hold it firmly in place to be screwed or unscrewed from the drill head. The auxiliary arm is considered necessary to reduce the physical demands on the astronauts.



## Dimensions and Hydraulic Cylinder Requirements of Auxillary Arm:

Effective Link Lengths of Auxillary Arm:

Arm:	Effective Link Length:
Arm #1	
Arm #2	ft.

Quantity, bore size, stroke length, and force capacities of cylinders:

Cylinder	s* Quantity	Bore Size	Stroke Length	Total Force
Arm #1 Arm #2	1 1	2 " 2 "	12" 10"	7,854 lbf 7,854 lbf
*note: A	All cylinder	s are doubl	e acting.	

The boom arm is designed to be attached to the tractor by means of a swing pivot assembly. The swing pivot assembly is to be attached to the tractor by means of a vertical plate and is to be capable of rotating through an angle of 180. in a horizontal plane. When connected to the swing pivot mechanism, the base of the boom arm is to be 3' above the ground.

General Comments: The final arm design was determined after much graphical evaluation of several possible solutions. Various constraints were used as different times to simplify the decision making processes involved. Contraints that were considered were: 1.) requiring that it be possible to drill the full range of angles at a single spot, 2.) requiring the middle joint of the arm to start from the same point for all possible linear strokes, 3.) requiring all drilled holes to be as close as possible to the base of the boom arm (to reduce movements), 4.) restricting the angular movement of each of the linkages of the arm (to reduce hydraulic cylinder stroke requirements). Not all of the constaints lead to a feasible solution for the design of the arm. In the end, the constraint which seemed the most practical was the one which limited the angular ranges of motion of the linkages. With this constrain in mind, the final design (as it now stands) was developed.

Drill String Assembly: The drill string assembly consists of 6 major parts: the drill head, the sub, the drill rods, the reaming shell, the core barrel assembly and the bit.

The drill head assembly converts hydraulic power into rotational motion to turn the drill rods and bit. A Longyear Hydra-Core 28 drill head is attached to the manipulator arm. It is hydraulically powered (2500 psi, 25 gpm) and comes with a 4 speed (including reverse) transmission that provides a bit speed range of 0 to 1250 rpm. The turning pin is size BQ; therefore, a BQ to NQ sub is necessary. The drill haed assembly also contains a swivel for lubrication flow.

A series 6 RED impregnated diamond bit is used. The bit selected is recommended for hard rock formations when using a hydrostatically powered drill head. Recommended bit speed, down hole pressure, and penetration rate are 100-1200 rpm, 6000-8000 lbf, and 3-4 inches per minute, respectively. The bit connects to a reaming shell with a circumferential diamond impregnated flange which cuts a clearance for the core barrel. The core barrel is connected to the reaming shell and the drill rods.

Foot Plate Assembly: The foot plate assembly lies over the drill hole on the moon surface. Its three major functions are:

- 1. Stabilizing and aligning the drill rods.
- Chucking the break-out drill rod when removing string pieces for dissembly or bit change.
- 3. Directing lubricant flow from the hole.

The first two of these are controlled by a pre-torque and break-out tool. It contains two sets of hydraulically actuated jaws that grip and rotate the drill rods. Lubrication flows through a sleeve assembly. This assembly is a 2 foot NW size casing attached to a side feed discharge swivel.

The footplate is a 4 foot by 4 foot by 1 inch plate of 2024 aluminum with a 6 inch by 24 inch clearance hole. A 35 inch long, 9 inch aluminum channel is welded on each side of the clearance hole. The pre-torque and break-out tool is bolted to the top of the channels to allow for positioning of the swivel assembly. The swivel assembly is bolted to the bottom of the foot clamp of the break-out tool by the swivel attachment pieces which are welded to the side discharge swivel.

This configuration is only appropriate for holes up to 45 degrees from vertical.

Core Retrieval: Since core samples may have to be retrieved from an angle, a pump-in type system will be utilized. This system consists of an overshot, side feed water swivel, a wireline stuffing box, and a hydraulic winch. The sub and head are removed from the rod and an Acker pump-in type "A" wire line overshot is inserted into the drill rod.

An Acker Side Feed water swivel is then attached to the drill rod. The swivel is preattached to a Mathey wire line stuffing box. The overshot cable runs through the stuffing box to a PullMaster PL-2 planetary hydraulic winch. This winch was chosen because it is totally enclosed, and the heat generated by the disc brake is dissipated by the hydraulic fluid of its motor.

Once the swivel is connected to the drill rod, pumping is resumed and the overshot moves down the drill string until it locks into the core barrel inner tube. Pumping is stopped, and the core is elevated by the winch. The swivel is disconnected from the drill rod, and the overshot and corebarrel are removed from the drill rod.

Pumping system for cooling and chip removal: In designing a lubrication system for a lunar core drilling apparatus, several factors had to be considered. Two of these are the low pressure atmosphere and the extreme temperature variations. On earth, water is the popular coolant and means of extracting the shavings from the bottom of the hole. The water is pumped down the center of the string, mixes with the shavings, and rises along the outside of the tube until it reaches the surface. However, the low lunar pressure would instantly vaporize the water: this was the first design problem.

While searching for an alternative substance, the extreme temperature variations must be kept in mind. As a solution to this problem, two possibilities were investigated. These were a silicone based oil and teflon beads. The beads were selected because of the chance of vaporization of the oil. Teflon has a high maximum operating temperature (500 degrees Fahrenheit) and will not gel at the low nighttime temperatures.

Because of the selection of the teflon beads, alternate equipment is required to handle the process. First, the pump must be able to transfer solids, therefore a progressing cavity pump was chosen. Another advantage of this pump is the continuous pushing action which provides minimum pulsation. Second, a process must be designed to enable the reuse of the beads. To solve this problem, an existing centrifugal cone filter was used. This filter forces the beads to the outside of the tank while the heavier shavings drop to the ground.

The pumping cycle begins with the pump pushing the teflon beads down the center of the string. Once reaching the bottom, the beads move outward through openings in the drill bit. This action permits the sweeping of the shavings out, up, and away from the drilling interface. As the mixture rises so does the heat. This is because 80% of the heat generated by drilling remains in the chips. This continuous process cools, cleans, and lubricates the system. Once the mixture reaches the surface, it is piped through the filter where the heated shavings are removed. The beads are passed onto the pump and the procedure continues.

<u>Control System:</u> The control system for the core drill unit consists of two parts: electrical and hydraulic. The electrical system is used for feedback signal processing, while the hydraulic system is used to move the actuators. A description of each system follows.

The heart of the electronic control system is a microprocessor  $(\mu P)$  or a programmable logic array (PLA). The choice between these two controllers would depend upon production quantities, with the PLA being more economical for large production runs. Typical operation of the electrical system involves processing of feedback information from the linear variable differential transformers (LVDT) located on each hydraulic cylinder. These sensors provide position and velocity information so that the controller may direct the drilling operation without the complexity of a vision system. The processor wses the difference between the known output and the feedback input to provide accurate closed-loop control. Also taken into account is the tractor orientation with respect to the vertical. Drill speed and direction of th rotation are controlled with a similar closed-loop feedback design.

The hydraulic system provides the muscle of the core drill unit. The double acting cylinders on the arms are controlled by Moog Model 642 3-way electrohydraulic servo valves. These valves allow precise control of the linear actuators. The drill motor and gripper are also controlled by valves of this type. Pressure reduction is accomplished with B&G,Ltd. pressure reduction units.

Communication/control by astronaut/operators is accomplished with a 2-way radio link. Feedback of all system parameters is available to the astronaut, and control parameters are entered as directed by the system. Drilling, lubrication, and bit-changing are controlled by system software, while breakout operations are manual due to their complexity. The entire system could be fully automated with further design time.

#### COMPLETE SYSTEM COST ANALYSIS

1.	ARM ASSEMBLY		
		MATERIAL COST	\$20,650.00
		DEVELOPMENT COST	\$22,000.00
_			
Ξ.	DRILLING ASSEMBLY	MATERIAL COST	കതത് മത്തെ ത്ത
		MATERIAL COST DEVELOPMENT COST	\$20,659.00 \$17,500.00
		DEVELOPMENT COST	#17, JUU. UU
3.	CORE RETRIEVAL SYSTEM		
		MATERIAL COST	\$2,069.00
		DEVELOPMENT COST	\$6,500.00
4.	LUBRICATION SYSTEM	MATERIAL COOT	يوديود سودان مسويت
		MATERIAL COST	\$5,145.00
		DEVELOPMENT COST	\$15,000.00
5.	CONTROL SYSTEM		
		MATERIAL COST	\$44,505.00
		DEVELOPMENT COST	\$13,000.00
	TOTAL COST		\$167.028.00

#### ARM COST ANALYSIS

QTY	DESCRIPTION	MATERIAL COST	LABOR HOURS	LABOR COST	TOTAL COST
1	POST PIN	\$50.00	25.0	\$1,250.00	\$1,300.00
1	TRACTOR MTG PLATE	\$180.00	20.0	\$1,000.00	\$1,180.00
1	PIN CAP	\$40.00	15.0	\$750.00	\$790.00
1	OUTRIGGER ASSY	\$150.00	30.0	\$1,500.00	\$1,650.00
2	SWING PLATE	\$100.00	5.0	\$250.00	\$700.00
1	GRIPPER	\$20.00	5.0	\$250.00	\$270.00
1	BOOM ARM	\$400.00	25.0	\$1,250.00	
1	MIDDLE ARM	\$150.00	15.0	\$750.00	\$900.00
1	DRILL ARM	\$80.00	9.0	\$450.00	\$530.00
1	AUX ARM # 1	\$80.00	9.0	\$450.00	\$530.00
1	AUX ARM # 2	\$100.00	12.0	\$600.00	\$700.00
5	SWING PINS	\$20.00	15.0	\$750.00	\$3,850.00
2	5" BORE X 40" STROKE	\$2,000.00	0.0	\$0.00	\$4,000.00
1	3" BORE X 40" STROKE	\$1,000.00	0.0	\$0.00	\$1,000.00
1	2" BORE X 20" STROKE	\$600.00	0.0	\$0.00	\$600.00
1	2" BORE X 12" STROKE	\$400.00	0.0	\$0.00	\$400.00
2	2" BORE X 10" STROKE	\$300.00	0.0	\$0.00	\$600.00
				\$0.00	\$0.00
				\$0.00	\$0.00
				\$0.00	\$0.00
				\$0.00	\$0.00
				\$0.00	\$0.00
				\$0.00	\$0.00
	TOTALS	\$5,670.00	185.0	\$9,250.00	\$20,650.00
	DEVELOPMENT COST				\$22,000.00
	TOTAL ARM COST				\$42,650.00

#### DRILLING ASSEMBLY COST ANALYSIS

QTY	PART	MATERIAL	LABOR	LABOR	TOTAL
	DESCRIPTION	COST	HOURS	COST	COST
1	BREAK OUT TOOL	\$9,750.00	Ø. Ø	\$Ø. ØØ	\$9,750.00
1	FOOT PLATE	\$150.00	8.0	\$400.00	\$550.00
1	DISCHARGE SWIVEL	\$425.00	2.0	\$100.00	\$525.00
2	SWIVEL ATTACHMENT	\$30.00	3.0	\$150.00	\$180.00
1	DRILL CASING	\$47.00	Ø. Ø	\$0.00	\$47.00
20	DRILL RODS	\$78.00	0.0	\$0.00	\$78.00
1	CORE BARREL	\$1,265.00	Ø. Ø	\$0.00	\$1,265.00
1	REAMING SHELL	\$230.00	0.0	\$0.00	\$230.00
1	DIAMOND BIT	\$435.00	0.0	\$0.00	\$435.00
1	BQ to NQ SUB	\$99.00	Ø. Ø	\$0.00	\$99.00
1	DRILL HEAD	\$7,500.00	0.0	\$0.00	\$7,500.00
	TOTALS	\$20,009.00	13.0	\$650.00	\$20,659.00

DEVELOPMENT COST \$17,500.00
TOTAL COST OF DRILLING ASSY \$38,159.00

#### CORE RETRIEVER COST ANALYSIS

QTY	PART DESCRIPTION	MATERIAL COST	LABOR HOURS	LABOR COST	TOTAL COST
1 1 1 1 1 1	OVERSHOT SWIVEL STUFFING BOX DERRICK STEEL CABLE WINCH	\$615.00 \$443.00 \$183.00 \$298.00 \$150.00 \$380.00	Ø. Ø Ø. Ø Ø. Ø Ø. Ø Ø. Ø	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$615.00 \$443.00 \$183.00 \$298.00 \$150.00 \$380.00 \$0.00 \$0.00 \$0.00 \$0.00
TO	TALS	\$2,069.00	Ø. Ø	\$Ø. ØØ	\$2,069.00

DEVELOPMENT COST

TOTAL COST OF DRILLING ASSY

\$6,500.00 ====== \$8,569.00

#### LUBRICATION SYSTEM COST ANALYSIS

GTY	PART	MATERIAL	LABOR	LABOR	TOTAL
	DESCRIPTION	COST	HOURS	COST	COST
1	PUMP	\$3,800.00	Ø. Ø	\$ଅ. ଅଅ	\$3,800.00
1	PIPE	\$25.00	2.0	\$100.00	\$125.00
1	PIPE	\$30.00	2.5	\$125.00	\$155.00
i	CONE FILTER	\$369.00	0.0	\$0.00	\$369.00
1	SILT POT	\$281.00	0.0	\$0.00	\$281.00
3	SWIVEL HOSES	\$130.00	Ø.Ø	\$0.00	\$390.00
1	COUPLING	\$25.00	Ø. Ø	\$0.00	\$25.00
				\$0.00	\$0.00
				\$0.00	\$0.00
				\$0.00	\$0.00
				\$0.00	\$0.00
TO:	TALS	\$4.660.00	4.5	 \$225. ₪0	\$5.145.00

DEVELOPMENT COST

TOTAL COST OF DRILLING ASSY

\$15,000.00 ====== \$20,145.00

#### CONTROL SYSTEM COST ANALYSIS

QTY	PART				
	DESCRIPTION	COST	HOURS	COST	COST
7	MOOG MODEL 642 VALVES	\$430.00	Ø. Ø	\$0.00	\$3,010.00
1	B&G PRESSURE REDUCER 3PS	5 <b>\$169.</b> 00	2.0	\$100.00	\$269.00
1	B&G PRESSURE REDUCER 7PS	6 \$155.00	2.5	\$125.00	\$280.00
140	VICKERS HYD HOSE	\$12.00	0.0	\$0.00	\$1,680.00
64	CONNECTORS	\$2.10	0.0	\$0.00	\$134.40
7	LVDT SENSOR	\$30.00	0.0	\$0.00	\$210.00
6	QUICK DISCONNECT		0.0	\$0.00	\$150.00
3	ANGULAR SENSOR	\$24.00	0.0	\$0.00	\$72.00
1	TRANSMITTER/RECEIVER	\$9,000.00		\$0.00	\$9, 000.00
1	COMPUTER CONTROLLER	\$16,000.00		\$0.00	. ,
1	SOFTWARE	\$1,200.00	250.0	\$12,500.00	\$13,700.00
	TOTALS	\$27,047.10	254.5	\$12,725.00	\$44,505.40
	DEVELOPMENT COST				\$13,000.00
	TOTAL COST OF DRILLING A	ASSY			\$57,505.40

#### HAZARD AND FAILURE ANALYSIS

The robot arm is to be, for the most part, automatically controlled. Thus, the astronauts should not be required to exert themselves excessively or dangerously while operating it. However, the astronauts must take care to ensure that the arm is controlled properly.

The possibility does exist that the drill system will malfunction. For example, the auxiliary arm may be ineffective or inoperative, thereby forcing the astronauts to do more manual labor. In addition, the main arm could bend or break or become severely out of alignment due to excessive stress or poor control. Such a malfunction could cause hydraulic fluid to leak or spew and could possibly injure astronauts in the vicinity. Therefore, it is recommended that the astronauts operate the arm by remote control from a safe distance. Drilling should be stopped whenever it becomes necessary for the astronauts to closely inspect or work with the machine.

There are three major areas where failure can occur in the drill string: hydraulic failure, loss of coolant down the hole and mechanical failure of some part of the drill string. A loss of hydraulic pressure will result in decreased motor speed and a loss of coolant to the motor causing it to overheat. This, however, is easily detected and drilling can be stopped before serious damage is done to the equipment. A pressure alarm or indicator gauge would decrease the likelihood of such an accident.

A mechanical failure down hole could be very serious. A broken or badly worn bit or rod would be very difficult and time consuming to repair. For such an occasion, certain fishing tools such as a rod, shell, and bit recovery taps should be included in the equipment taken to the moon.

The loss of lubricant down hole is a serious problem. It both cools the bit and removes the chips generated by drilling. If the lubricant flow is restricted or cut off, frictional heat and chips build up causing large mechanical and thermal stresses in the bit and rods. This sort of failure could result in the loss of the bit, reamer shell, and core barrel.

The core retrieval system is also subject to failure. This system can fail if the overshot will not lock onto the core barrel or if the cable snaps during hoisting. If this occurs the overshot should be hoisted up and reinserted, if this still fails the string will have to be dismantled to retrieve the core.

#### OPERATING INSTRUCTIONS

#### 1. Site Preparation

- a. Clear lose and broken rock.
- b. Drill starter hole at desired angle, 2' X 3.5"dia.
- c. Insert swivel sleeve into hole.
- d. Set breakout tool angle and position over hole such. that swivel attachment holes are in line.
- e. Attach swivel.
- f. Position drill arm, rod rack, pumps, and derrick.
- g. Attach hydraulic lines.

#### 2. String Preparation

- a. Attach bit, reamer shell and core barrel.
- b. Lift assembly with auxiliary arm and insert it into the breakout tool.
- c. Lower until one half foot of barrel remains over tool, then chuck the barrel.
- d. Release auxiliary arm.

#### 3. Drilling

- a. Lift and position drill rod.
- b. Connect drill head to drill rod and drill rod to to section remaining above the breakout tool.
- c. Start lubrication flow.
- d. Unchuck the rod.
- e. Start drill motor and drill for the 5 foot stroke.
- f. Stop drilling.
- g. Chuck rod in place.
- h. Stop lubrication flow.
- i. Empty chip pot.
- j. Detach drill head.
- k. Move arm up.

#### 4. Core Retrieval Procedure

- a. Use auxiliary arm to position and insert the overshot into the drill rod.
- b. Lower the overshot as far as possible. (If overshot lowers enough to lock onto core barrel the following steps are not necessary.)
- c. Attach the swivel/stuffing box assembly to drill rod.
- d. Start pumping lubricant, until overshot locks onto core barrel.
- e. Stop pumping lubricant.
- f. Detach swivel/stuffing box assembly.
- g. Hoist core up and out of the drill string.
- h. Grasp core barrel with auxiliary arm.
- i. Disconnect overshot from core barrel.
- j. Raise overshot and swivel/stuffing box assembly out of the way.

- k. Remove core from core barrel and place it into core box.
- Return core barrel to drill string and lower it. (or continue with Step 6)
- 5 Repeat steps 3 and 4 until desired drilling depth is obtained.
- 6. Drill String Dissembly
  - a. Connect drill head to drill rod.
  - b. Unchuck drill rod.
  - c. Raise the string five feet. (First rod only raise 2 feet)
  - d. Use foot clamp to hold drill rod.
  - e. Use break out tool to break out drill rods.
  - f. Unclamp drill rod.
  - g. Lift string five more feet.
  - h. Clamp drill rod.
  - i. Disconnect top drill rod using auxiliary arm.
  - j. Return rod to the rack.
  - k. Connect drill head to top drill rod.
  - 1. Repeat steps 6e. thruogh 6h. until all drill rods are removed.
  - m. Remove core barrel, reamer shell, and bit from last tube.
  - n. Reverse steps 1a. through 1g. to dissemble site equipment.

#### CONCLUSIONS AND RECOMMENDATIONS

The proposed lunar core design contains several interesting innovations and deserves further study. In particular the three areas that require the most attention are: 1) arm design, 2) Teflon bead lubrication, and 3) automation.

#### Arm Design

Having a robotic arm similiar to a backhoe in the design of the lunar core drill is very interesting and certainly practical in the sense that the arm can be used both for core drilling and for lunar excavation. However, the hydraulic forces required to operate such a dual purpose arm are extremely high and border on impracticality. Possible kinematic improvements on the design of the arm need to studied extensively.

#### <u>Teflon</u> Beads


Using Teflon beads for lubrication, cooling, and chip removal also extremely promising idea, but untested. necessary Experimentation is to properly evaluate effectiveness of the beads. In addition, further consideration needs to be given to the possible drawbacks of the Teflon beads; namely: 1) Unwanted smearing of the hole with a thin Teflon film, 2) difficulty in efficiently separating the beads from the chips. 3) difficulty in removing the beads from the hole once drilling is complete, and 4) severe scarcity and prohibitive cost Teflon beads in the size and quantity desired.

#### Automation

Further study needs to be done to create more reliable automatic control systems for the core drill. In particular, a good deal more work should be done on controls that are very sensitive to changes in the down hole situation, i.e., changes in lubricant pumping pressure, changes in vibration of the drill, and changes in the rate of penetration.

APPENDIX

CALCULATIONS/ COMPUTER USAGE



 $\sum F_{x} = R_{x} + 7270 \cos t + R \cos t \cos \theta - 11273 \text{ lbs} = 0$   $\sum F_{y} = R_{y} - 7270 \sin t - R \cos t \sin \theta + 9290 = 0$   $\sum M_{0} = 7270 (\cos t') 3.25 + R \cos t (\sin \theta) 7 - 9290 (8) = 0$ 

4'+4=67.4°

E'<0<15; 0<4<6 61.4<4'<67.4

Royl = 92908(8) - 7270 (3.25) cos (1)
Tsino

= 9290(8) - 7270 (3.25) cos (61,4)
Tsin 8°

= 64,700 lbs.

Use 2 cylinders, 1.5 safety factor Royls = (64,700(1.5)) = 48,500 lb. each.

48,500 lb. = 19.4 in 2

<u>πα</u>= 19.4 α = 4.97 use(2)5" cylinders with 40"stroke.

## Pin Reactions

$$6.06 = \frac{\pi d^2}{4}$$
 $d = 2.77$ 
use a 3"pin

204 Hrm Calculations

 $V_{y} = R_{x} - 6800 - 2110 \cos\theta - Royl \cos 4 = 0$   $V_{y} = R_{x} - 6800 - 2110 \cos\theta - Royl \cos 4 = 0$ 

 $ZF_{X} = R_{X} - 6800 - 2110 \cos\theta - Royl \cos 4 = 0$   $ZF_{Y} = R_{Y} + Royl \sin 4 + 2110 \sin \theta + 1730 = 0$  $ZM_{0} = -1730(3ft) - 2110(1.11ft) \sin 5 + Royl(1) \sin 4 = 0$ 

-1730(3) -2110(1.11)sin57° + Royl sin 76° =0 Royl = 2426 lbs

at 0 = 14° 5 = 46° 4 = 71°

-1730(3) -2110 (1.11) Sin 46° + Royl Sin 71° = 0 Royl = 7270165. max.

Sizing Cylinder

7270 165 - 2.90in² × 1.55afety - 4.36 in²
2500 psi factor

9703 = 4.36 in 2 STroke = 4 a2 = 5.55 in

a=2,35 use (1) 3" borglinder

2nd Arm Calculations.

Rx = 6800 + 2110 cos 30 + 7270 cos 710

Rx = 11273 ebs.

- Ry = -7270sin 76° +2110 Sin 14° +1730

-Ry = 9290 ebs.

Rmax = V 112732 + 92902 - 14,610 lbs.

Lying Pen at joint

T = 5

Ssy = T = 15.0 kpsi

F = 14,610 lbs

A = 14,610 = ,975 x1.5 foct. 50/ety =

1.46 in 2

 $\frac{\pi d^2}{4} = 1.46$   $d^2 = 1.86$ 

d= 1. 36 in

Juse a = 1.375 in ]

# CALCULATIONS: DRILL ARM (3rd Arm)

$$\Rightarrow \sum F_X = Royl \cos\theta + Rx - 8000 = 0$$

$$1 \sum F_Y = -Royl \sin\theta + Ry = 0$$

From the feinematics 
$$V = 0.7.6^{\circ}$$
  $-14.6 < 4^{\circ}$   $-7^{\circ} < 0 < -35^{\circ}$   $< 01.6^{\circ}$ 

In this position:

Maximun shear on pin =

$$\sqrt{R_{ymax}^2 + R_{xmax}^2} = \sqrt{Z/10^2 + 8000^2} = 8270 \text{ lbs}$$

Using Stel with 
$$S_y = 26$$
 kpci  
 $S_{0y} = .577 S_y = 15.0$  kpsi  
Ashear =  $\frac{E}{S_{0y}} = \frac{8370}{15,000} = .55$  in <sup>2</sup>

# DRILL'ARM CALCULATIONS (con't)

Ashear = .55in2

11=1.5

As=, 827m2= 7Td2

 $d^2 = 1.05$ 

d= 1.026 in

une d = 1.125 in for pun joint

Sizing cylinder we-know stroke-length=19"

Fayé = 2110 lbs

Pressuré = 2500 psi

N = 1.5

Aria of cylinder = 3165 - 265 = 1.26 m²

boré 2500 psi

Ta= 1.26 in<sup>2</sup>

d2=1.6/in

d= 1.26in

I" bou will not work

use à 2" vore; 20" stroke

## SWING PIVOT FRAME CALCULATIONS

## SUPPORT PLATE:

(Buckling) Pce= 
$$Pn$$
,  $P=60,000$  lbf,  $n=3$   
Pce= 180,000

= .0994in4

SUBSTITUTING YIELDS

$$\frac{1}{K} = \frac{14}{.289.492} = 98 \quad \text{if } (\frac{1}{K}) = \sqrt{\frac{277^{2}CE}{Sy}} \quad \text{Sy} = 84x10^{3}$$

$$(\frac{1}{K}) = 92$$

Therefore this is an Euler Column and this criterion is valid. (Deflection)

For Zin. thickness

This will serve as a first approximation when supports are added deflection will be checked.

## RING RETAINING BOLTS:

Shear load = 122,000 lbf 
$$A = Cross-sectional$$
 Area of boths
$$J = F/A = \frac{122,000}{6 \times \frac{\pi (75)^2}{4}} = 46,025 \text{ psi}$$

maximum allowable shearstress T = .5 Sy There fore use SAE grade 8 CAPSCREWS (.75"dia) Sy = 130 ×10<sup>3</sup>psi  $T = 65 \times 10^3$ psi

## OUTRIGGER ARMS

I = 1993in4

$$Pcr = \frac{122000}{2} = 61,000/64$$
 $T = \frac{61,000 p^2}{CE\pi^2}$ 
 $l = length of arms = 70''$ 
 $C = 1$  (both rounded)

$$I = \frac{bh^{3}}{12} \quad b=3in.$$


$$h = \begin{bmatrix} 12 & 1 \end{bmatrix}^{3} = 1.6 in$$

$$\begin{cases} 1 & 1 \\ 1 & 1 \end{bmatrix} = \frac{70}{1289(1.6)} = 151$$

From previous calculations

## SUPPORT SIZING:

$$\Sigma M_o = -14(122,000) + 2.$$



$$X = 726,808$$

There are 2 parallel supports therefore each handles 1/2 the total load.

$$I = \frac{P_{cr} \int_{0}^{2} E}{C \pi^{2} E}$$

=.0056

 $I = \frac{Por}{C \pi^2 E}$  I = length of column = .0056 I = length of column = columnb= width of column

There fore. 25 in sheet steel is used for support.

## POST PIN

Bearing stress in past pin:

A = td where t= thickness of bearingplate d=diameter of pin.

F= 180,000 lbf

MAXIMUM allowable shear stress

# LUBRICATION & COOLING

#### TEFLON CHARACTERISTICS

 $S_{comp} = 1700$  psi  $S_{ut} = 4500$  psi  $H_{ROCK.} = 28$  (R-SCALE) POISSON'S RATIO =  $\eta = 0.46$  @  $73^{\circ}F$ SPECIFIC GRAVITY = 2.2WATER ABSORBTION = 0.005%THERMAL CONDUCTIVITY = k = 1.5  $\frac{8}{hr}H^{2} F$ MAXIMUM TEMPERATURE =  $500^{\circ}F$ DENSITY = Q = 134.16  $\frac{15}{H^{3}}$ NON-FLAMMABLE

## CALCULATIONS

EARTH CONDITIONS FOR DRILLING
- PENETRATION RATE 4 "/min
- WATER FLOW RATE 9 -> 12 gal/min
1,2 -> 1.6 ft3/min

DUE TO HIGHER THERMAL CONDUCTIVITY AND HIGHER OPERATING TEMPERATURES, SIMILAR FLOW RATE CAN BE ASSUMED

FLOW RATE = 10 gal/min = 1.34 fl/min = 0.022 ft/sec

IN A 1½" PIPE AREA = 1.77 IN² = 0.0123 ft² : VELOCITY = V = 0.022  $\frac{ft^3}{\sec} \times \frac{1}{0.0123 ft^3} = 1.79 \frac{ft}{\sec}$   $\dot{m} = eVA = (134 16 \frac{b}{ft^3})(1.79 \frac{ft}{\sec})(0.0123 ft^2)$ = 2.95 /sec

## LUBRICATION & COOLING (CONT.)

HEAD LOSS IN PIPE

$$h_{L} = 2f_{f} \frac{L}{D} \frac{v^{2}}{g}$$

$$L = 100 \text{ ft}$$

$$D = 0.25 \text{ ft}$$

$$V = 1.79 \text{ ft/sec}$$

$$g = \frac{32.2}{6} = 5.33 \text{ ft/sec}^{2}$$

$$f_{f} = 0.006$$

$$h_{L} = 2(0.006) \cdot \frac{100}{0.25} \cdot \frac{(1.79)^{2}}{5.33} = 2.89 \text{ ft}$$

PRESSURE DIFFERENCE = DP = 55 psi

LOOKING IN ROPER PROGRESSING CAVITY CATALOG, THE PUMP BEST SUITED FOR OUR PURPOSE IS STK # 71202 WITH THE FOLLOWING CHARACTERISTICS:

	Gal	PUMP SPEED DIFF, PRESS. psi	300 RPM GPM MIN HP		GPM MIN.HP		900 RPM GPM MIN.HP	
	- 'CV	DIPP, PRESS, ISI	GIAL	7-11/4 10	Grie	PIIN THE	GPM	79174. HT
71202	2.02	0	5.8	1/2	12.0	1/2	18	3/4
		40	4.0	1/2	9.5	1/2	16	}
		75			5.5	3/4	12	1/2

#### Computer Usage

Computer usage was very minimal in our design. The area in which it could have helped us the most was in the design of the arm. The use of a CADD system would have cut design time and allowed for a more meaningful optimization process. HP-41CV's were used in determining weld sizes and doing stress analysis on some members.



## PARTS LIST

ITEM	DRAWING NUMBER	G DESCRIPTION	MFGR	PART #	WEIGHT LBF	QUANTITY
_	_	ARM ASSEMBLY	_		<del>-</del>	
1	101	TRACTOR MOUNTING PLATE	_	~	570	1
2	102	POST PIN	_	_	250	1
3	103	PIN CAP	_	_	10	1
4	104	OUTRIGGER ASSY	_	=	213	2
5	105	SWING PLATE	_	_	50	2
6	106	GRIPPER	_	_	10	1
7	107	BOOM ARM	_	<del></del>	850	1
8	108	MIDDLE ARM	_	_	36 <b>0</b>	1
9	109	DRILL ARM		_	110	1
10	110	AUX ARM #1		-	50	1
11	111	AUX ARM #2	-	_	72	1
12	112	SWING PIN	-	-	8	1
13	113	SWING PIN	_	-	8	1
14	114	SWING PIN	_	-	7	1
15	115	SWING PIN		_	7	1
16	116	SWING PIN		_	7	1
17	117	5" BORE X 40" STROKE	ENERGY	CRT-500		2
18	118	3" BORE X 40" STROKE	ENERGY	CRT-300	100	1
19	119	2" BORE X 20" STROKE	ENERGY	CRT-200	65	1
20	120	2" BORE X 12" STROKE	ENERGY	CRT-200	50	1
21	121	2" BORE X 10" STROKE	ENERGY	CRT-200	43	2
-	200	DRILLING ASSY	-	<b></b>	_	_
1		PRETORQUE & BREAKOUT TOO	LLONGYEAR	41600	750	1
2	201	FOOT PLATE	_	-	232	1
3		SIDE FEED DISCHARGE SWIV	E ACKER	21060-5	30	1
4	202	SWIVEL ATTACHMENT		-	1	2
5	-	NQ DRILL CASING 2'			17.4	1
6	_		LONGYEAR		26	20
7		PUMP-IN TYPE A WL CORE				1
8	~	REAMING SHELL	LONGYEAR			1
9		SERIES 6 RED IMPREG BIT				1
10			LONGYEAR		5	1
1 1		HYDRACORE 28 DRILL HEAD		-	218	1
~~		1/2-20UNF BOLT 1.25 LONG	_	-	_	10
-		1/2-20UNF NUTS	_	~	-	6
-		1/4-28UNF 1.0 LONG BOLTS		_	-	4
		CORE RETRIEVAL ASSY			-	
1		PUMP IN OVERSHOT	ACKER	10123	22	1
2		SIDE FEED H20 SWIVEL				1
3	_	WIRELINE STUFFING BOX	MATHEY	STUFF B	12	1
4		ALUM. TRIPOD DERRICK				100'
5		3/16" HOIST CABLE		21035-6	62	1
6	-	PLANETARY HYDR. WICH	PULL MAST	TPL2-12-	174	
	400	LUBRICATION SYSTEM ASSY		_		_
1	401	PROGRESSING CAVITY PUMP	ROPER	71202	210	1
2		TANK/PUMP CONNECTING PIPE		-	162	1
3		FILTER CONE/TANK PIPE			1	_
4	-	4" FILTER CONE ASSY	COOPER	2570-22		1
5	_	SILT POT ASSY			50	1


## PARTS LIST

ITEM	DRAWING NUMBER	DESCRIPTION	MFGR	PART #	WEIGHT LBF	QUANTITY
6	-	1.25 NPT H20 SWIVEL HOSE	LONGYEAR	18912	18	3
-		WATER SWIVEL COUPLING	LONGYEAR	18910	3.5	1
-	-	3/4-16UNF BOLTS			_	8
-		3/4-16UNF NUTS	_	-	-	8
-		5/8-16UNF BOLT	-	_	-	8
_	-	5/8-16UNF NUTS		_		8
	-	TRIFLON MICRO-BEADS	CLIFTON	-	1790	LOTS
	500	CONTROL SYSTEM DIAGRAM		-	-	-
_		ARM #1 HYDRAULIC CIRCUIT		-	-	-
-		ARM #2 HYDRAULIC CIRCUIT		~		_
	503	DRILLING CONTROLS	_		_	-


7107.9

SITE ASSITIONS DING VIN 001






(747)



ARM FIZZERELY TRANSPORT POSITION


ORIGINAL PAGE IS OF POOR QUALITY

101- TRACTOR KNUNTING PLATE







ENG 10. 17.3 10.35 STEEL




57EEL


MAT.: 1035







OF POOR QUALITY









ORIGINAL PAGE IS OF POOR QUALITY



36.  $\mathcal{S}$ 4





ORIGINAL FAGE IS OF POOR QUALITY






ORIGINAL FRAGE 13 OF POOR QUALITY






ORIGINAL PAGE IS OF POOR QUALITY


PIN No.	"A"	"B"
112	11.0	3.0
//3	/3.0	7.375
114	13.0	1.5
//5	11.0	1.6
116	7.0	1.0



<u>5WING PINS</u> 1035 STLEL DWG 112





7.80 J	11	8//	6	00	121
NOVE -	500	18-37 18-25	200	100	18
				7	V 1
7	6 6 W2 123, 2- 5 2 - 1 5 235 Con 30	14 23	43 (3) (4)	61	(A)
la.	1	77			
		;	40	1. 10	1
7	, J	r) CG	Try.	( j )	No.
)		<b>K</b> .	(I)	· · γ	7)
×.	(4)		N.	(-1	· .
		Ę.,	1. D	63	,n,
-£	11/2	30	. g.	~ 1 ~	€ ====================================
U	e. P	7.343	8	<i>w</i>	<i>w</i>
E	ω <sub>2</sub> ,	S	10 10	100 100	30
$_{i}\cap$		7	2,7	.7	53
	1/2	2, 2	4		
a)	13	7	( 	2	23: 53. 33.
7	740	8	B	84	3
BONG STRIK A B C	5 40 4.02 1/2	3 40 50,4 106 12	13	2 12 27-18.38	0
80,2	$\mathcal{O}$	B	d	U	
DR90	111	8//	6//	120	121



DEVILLAGE FORE

CHARTE PARE IS





ECCT PLATE

SMITHK TOUR C.

TO SECTION SEC

- 1/4 - X

DEN LA. : With Milling Pales

6.00


FALFY NELFOLD





Walter Charles


(BUTTER TO FOUR CLAMETON ASSIV W. 256-78-19 8000) DAYS NO. 202

ORIGINAL PAGE IS OF POOR QUALITY











PROGRESSING CANTY PUMP




ORIGINAL PAGE IS OF POOR QUALITY


OF PLAN MINING




PRM #2 HYDRAULIC CIRCUIT



OPERATING POSITIONS OF THE ARM



POSITIONS OF
ARMS FOR A
VERTICAL
HOLE:
TOP AND
BOTTOM



Insert Position PRMS TO
Pick-up Position ADD DRILL
STRING PIECES!

ground

#### ALTERNATIVE DESIGNS

Despite all attempts, the design of the lunar core drill presented in this report may not represent the best solution possible. The following alternative designs are ones which were not evaluated extensively but may actually have contributed to a better overall solution.

### Design of Arm

An alternative method for designing the arm would have been to simply use a Longyear Hydra Core 28 core drilling unit, mount it rigidly to a platform, and attack the platform to the tractor swivel. In this case, the platform or 'arm 'would only have to pivot in a horizontal plane and would not be required to form angles in a vertical plane. The Hydra Core 28, itself, would be capable of making the required Ø to 90 degree angles with respect to vertical and would supply its own downward hydraulic drilling force. Such a design would be simple compared to the 'backhoe' arm design and would require much lower hydraulic forces. Such a design, however, would not be able to function both as a core drill and a lunar excavator. At any rate, the design does seem promising.

## Design of Lubrication System

As mentioned before, several ideas were considered and could be used as a future alternative design. Instead of using Teflon beads, a silicon-based oil might be substituted. The oil has a high maximum operating temperature and consistent viscosity at a variety of temperatures. However, the possibility of flashing would require a completely closed system which is difficult to design. Also, oil would leave a messy film on the sides of the hole that would restrict the use of a borescope. On the other hand, a conventional pump could be used and a less complicated filtering system could be designed. Whichever process is chosen, it must undergo much testing before its operation begins.

Another solution to this problem is to have no lubricant at all. In such a case, a dry hole would be drilled and augers on the end of the drill string would be used to collect the chips. Such a design has been experimented with before but has never worked flawlessly. The design is attractive, however, due to the fact that it requires no pump, no strainer system, and no evaporative or fluid loss considerations.

## REASONS FOR NOT PURSUING LASER DRILLING

Drilling of lunar soil with a laser beam was suggested as an alternative to conventional, impractical methods such as a mechanical bit with a motor drive. It appears, from an overview of rock thermodynamics, that drilling of basalt with a laser may be possible with further research. All properties found were consistent with good thermal drilliability; abrasiveness makes mechanical drillibility difficult.

Some properties of basalt were found in various literature. A partial listing appears below:

Thermal conductivity [J/m sec C]	1.25 - 2.93
Heat capacity [J/g C]	0.63 - 0.90
Coefficient of linear expansion [1/CxE-5]	0.54
Modulus of Elasticity [kg/cm^2xE-5]	9.0 - 12.0
Poisson's ratio	0.24
Ultimate compressive strength [kg/cm^2]	300 - 400
Ultimate shear strength Ekg/cm^2]	175 - 460
Melting Temperature [ K]	1310
Texture	Fine grained, glassy


"The coefficients of linear and volume expansion of rocks are the most important thermo-physical characteristics governing their capacity to transform heat into mechanical energy."( )

Coefficient of volume expansion = 
$$\frac{\text{wi Ki Vi}}{\text{Ki Vi}}$$
 where 
$$\text{Ki = thermal conductivity of component i}$$

wi = coefficient of thermal expansion of component i

These characteristics may be construed to prove that basalt is an excellent candidate for laser drilling. It melts rather than breaking, making removal from the hole by evaporation possible. Heat of vaporization data could not be located, so that problems of condensation could not be considered. A high heat of vaporization would make material removal easier.

 $\forall i = \forall olume of component i$ 



The only reason for not considering the laser drilling option is the enormous power consumption of the laser, on the order of several kilowatts. This much power is not available in our design constraints. These design constraints should be reviewed and possibly changed in order to consider this option.

() Rzhevsky, Y. and Novik, G., (1971), <u>The Physics of Rocks</u>, Moscow: Mir Publishers, pp. 149, 285-290.

#### BIBLIOGRAPHY

Acker, William L. <u>Basic Procedures for Soil Sampling and Core Drilling</u>. Scranton, PA; Dristributed by Acker Drill Co.; 1974. 246 p.

Bailey, C.; Aarons, J. <u>The Lubrications Engineers Manual</u>; United States Steel Corporation; 1971. 460 p. (p. 358) "Basic Hydraulics"

Gamon, George. The Moon: New York: Abeland-Schuman; 1971. 126 p.

Higgins, Lindley R. <u>Handbook of Construction Equipment</u> Maintenance. New York: McGraw-Hill;1979. 957p. (p. 711)

Stuart, Ross Taylor. <u>Lunar Science: A Post Apollo View</u>. New York:Pergamon Press, Inc. 1975

"Progressing Cavity Pump", Bulletin 79-79, Roper Pump Company, Revised 5-80

"Field Manual", Longyear Company, 1981

"Hydra Core 28 Drill, Operations and Service Manual", Longyear Company, 10-1982

"Diamond Drilling Equipment", Equipment Catalog, Longyear Company

#### ACKNOWLEDGEMENTS

Randy Klinger, Industrial Tectonics, Ann Arbor, Michigan (313) 426-4681

Joe Robinson, Sales Engineer, Clifton Plastics, (215) 622-3900

Terry Stachur, Tadco Systems, Atlanta, GA, (404) 972-6660

Linda Moeller, Dupont Technical Information Hotline-Teflon Products, 1-800-441-7515

Lynn A. Holmberg, Sales Service Technician-Central U.S.A., 925 Delaware Street S.E., Minneapolis, Minn. 55414, (612)-331-1331

## This is an important legal document. Read instructions carefully before filling in data.

PROJECT NO.		IR I TY	REC. OF		
CONTRACT NO.			INV. NO		
1. NAME OF INVENTOR			POSITION		
GEORGE PAUL 8	BURDELL	$U^{\wedge}$	IDERGRADUATE	STUDENT	
NONE 3. DATES OF EMPLOYMENT					
NONE	<del></del>				
4. PRESENT ADDRESS ( No. Street, City, Cour 225 NORTH AVENUE 5. PERMANENT ADDRESS ( No. Street, City, Cou	. ATLANTA FU	LTON, GA (404) 8		MANENT	
6. NAMES (S) AND ADDRESS (ES) OF CO-INVENTORS  BARRY M. FRENCH -	•	NANCY J	EAN SHALER -	SAME	
MATTHEW L. ADAMS	S - SAME	MARK S	HAJOS	SAME	
7. DESCRIPTIVE TITLE OF INVENTION	R-SAME	KURT O	MUNNIG -	SAME	
8. LIST DRAWINGS, SKETCHES, PHOTOS, REPORTS. $NUNE$	DESCRIPTIONS, NOTEBOOK ENTRIE	ES, ETC. WHICH SHOW OR DESC	RIBE INVENTION		
9. EARLIEST DATA AND PLACE INVENTION WAS CON			VIED O LINE	00 1125	
	,		VED A LUN		
276100	IN SITE P	REPARATIO	N OF A L	UNAR	
SPACE STATION					
MANAGES					
10. DATE AND PLACE OF FIRST SKETCH, DRAWING O  4 APCIL 1985 ON  11. DATE AND PLACE OF FIRST WRITTEN DESCRIPTI		OR OF PRIC	E GILBERT MEN	MORIAL LIRRAR	
11. DATE AND PLACE OF FIRST WRITTEN DESCRIPTI	ON			<u> </u>	
12.	DISCLOSURE OF INVE	ENTION TO OTHERS			
NAME, TITLE AND	ADDRESS	FORM OF	DATE AND PLACE OF DISCLOSURE	WAS SIGNATURE OBTAINED	
		DISCESSORE	0r 01302030N2	(YES OR NO)	
NONE					
				<u> </u>	
			· · · · · · · · · · · · · · · · · · ·		
12.A IMPORTANT - HAVE ANY PUBLICATIONS OR RE	BODTO OCEN MADE ON THIS INVENT	10113		<u> </u>	
N()	TONIS BEEN MADE ON THIS INVENT	TORY			
13. DATE AND PLACE OF COMPLETION OF FIRST OPE	/	CE			
DOES NOT AP 14. PRESENT LOCATION OF MODEL	PPLY		* ·		
DOES NOT A	PPLY				
15. DATE, PLACE, DESCRIPTION AND RESULTS OF F					
DOES NOT	APPLY				

16. NAMES AND ADDRESSES OF WITH	ESSES OF FIRST TEST	T				
DOES	NOT API	PLY				
7. DATE, PLACE, DESCRIPTION AN	D RESULTS OF LATER	TESTS (name with	esses)			
DOES.	NOT A	PPLY				
				<del> </del>		
18. IDENTIFY RECORDS OF TESTS A	IND GIVE PRESENT LO	CATION OF RECORDS	S			
DOES	NOT A	PPLY				
	. <u></u>	· · · · · · · · · · · · · · · · · · ·				
	70 70 70	W LUNGSTION IS DE	TLATED			
19. PRIOR REPORTS OR RECORDS OF	INVENTION TO WHIC	A JAVENTION 15 NO				
20.	OTHER KNOWN CLOSELY RELATED PATENTS, PATENT APPLICATIONS AND PUBLICATIONS					
PATENT OR APPLICATION NO.	DATE	TITU	E OF INVENTION OR PUBLIS	HED ARTICLE	NAME OF PUBLICATION	
NONE						
			<u></u>			
	<u> </u>					_
21. EXTENT OF USE: PAST, PRESE					APPARENT	
THIS TIME	, FUTU	RE USI	E WILL	BE BY	NASA PICIO	OR TO
LUNAR CON	STRUCT	10N.		LI OW LING COMPAN	IES UD VELLAILIES	
		TION HAVE BEEN	RELEASED TO THE FO		CONTRACT NO.	DA TE
NAME AN	D ADDRESS		INDIVIDUAL ON REV	ACSENTATIVE		<u> </u>
<u>NONE</u>						
	Q	PO	R. J.M			2 Aug 198

SIGNATURE OF INVENTOR

Duraell

#### (Attach to Record of Invention Part 1)

REC. OF	
INV. NO.	

This Disclosure of Invention should be written up in the inventor's own words and generally should follow the outline given below. Sketches, prints, photos and other illustrations as well as reports of any nature in which the invention is referred to, if available, should form a part of this disclosure and reference can be used thereto in the description of construction and operation.

1. INVENTORS NAME (S)

GEORGE PAUL BURDELL

2. FILLE OF INVINTION

LUNAR CORE-DRILLING APPARATUS

For answers to following questions use remainder of sheet and attach extra sheets if necessary,

- GENERAL PURPOSE OF INVENTION. STATE IN GENERAL TERMS THE OBJECTS OF THE INVENTION.
- 4. DESCRIBE OLD METHOD (S) IF ANY, OF PERFORMING THE FUNCTION OF THE INVENTION.
- 5. INDICATE THE DISADVANTAGES OF THE OLD MEANS OR DEVICE (S).
- 6. DESCRIBE THE CONSTRUCTION OF YOUR INVENTION, SHOW-ING THE CHANGES, ADDITIONS AND IMPROVEMENTS OVER THE OLD MEANS OR DEVICES

- GIVE DETAILS OF THE OPERATION IF NOT ALREADY DESCRIBED UNDER 6.
- 8. STATE THE ADVANTAGES OF YOUR INVENTION OVER WHAT HAS BEEN DONE BEFORE.
- 9. INDICATE ANY ALTERNATE METHODS OF CONSTRUCTION.
- If a Joint invention, indicate what contribution was made by fach inventor.
- 11. FEATURES WHICH ARE BELIEVED TO BE NEW.
- 12. AFTER THE DISCLOSURE IS PREPARED. IT SHOULD BE SIGNED BY THE INVENTOR(S), AND THEN READ AND SIGNED AT THE BOTTOM OF EACH PAGE BY TWO WITNESSES USING THE FOLLOWING STATEMENT:

THE PURPOSE OF SAID INVENTION IS TO OPERATE AS A CORE-DRILLING MECHANISM UNDER LUNAR CONDITIONS. THIS MACHINE MUST BE ABLE TO WITHSTAND LOW PRESSURES AND HIGH TEMPERATURES, YET BE OPERABLE BY AN AUTOMATED SYSTEM.

EXISTING TECHNOLOGY IS LIMITED TO EARTH - BOUND THIS GENERAL METHOD INVOLVES THE USE OF EQUIPMENT. WATER AS A LUBRICANT, COOLANT, AND MEANS REMOVING THE CHIPS FROM THE BOTTOM OF THE HOLE. ANOTHER CHARACTERISTIC OF PRESENT EQUIPMENT IS MOUNTING ON A TRAILOR WHICH PERMITS EASY MOBILITY PROCEDURE BEGINS WITH THE DRILL PROGRESSING THE WHILE THE WATER IS PUMPED INTO THE CENTER OF BY PASSING THROUGH THE TEETH STRING. THE WATER COLLECTS THE SHAVINGS AND CARRIES THEM UPWARD ALONG THE OUTSIDE OF THE SHAFT. GENERALLY IS ALLOWED TO SPREAD MIXTURE OVER THE GROUND

DUE TO THE INFERSIBILITY OF EXTRACTING THE WATER. WHEN AN ADDITIONAL LINK IS NEEDED, THE PROCESS STOPS AND CREWMEN MANUALLY JOIN THE NEW PIECE. INV. NO.

DISADVANTAGES OF THIS EXISTING SYSTEM ARE:

- 1. WATER CAN NOT BE USED IN THE LUNAR ENVIRONMENT BECAUSE IT WOULD VAPORIZE DUE TO THE LOW PRESSURE; THEREFORE ANY LIQUID LUBRICANT OR COOLANT WOULD HAVE TO OPERATE IN A COMPLETELY CLOSED SYSTEM.
- 2. AUTOMATIC CONTROLS MUST MONITOR ALL EQUIPMENT BECAUSE OF THE INABILITY TO "SENSE" HOW A PART IS OPERATING, ALSO, MANUAL LABOR IS NOT PRACTICAL BECAUSE OF THE BULKY SPACE SUITS WHICH RESTRICT MOST MOVEMENT.

TO MAKE A CORE DRILL SUITABLE FOR LUNAR OPERATION, SEVERAL CHANGES WERE MADE. FIRST, SOLID TEFLON BEADS WERE SUBSTITUTED FOR WATER, THUS AVOIDING THE POSSIBILITY OF FLASHING. THE BEADS WILL BE HANDLED SIMILARLY TO WATER EXCEPT A COMPLEX FILTERING SYSTEM WILL BE ADDED SECONDLY, ALL MACHINES WILL BE INTERCONNECTED THROUGH AN AUTOMATIC CONTROL NETWORK. THE ASTRONAUT WILL THEN BE ABLE TO MONITOR THE ENTIRE SYSTEM FROM A CENTRAL POST. FINALLY, THE CORE DRILL OPERATES SIMILARLYTO A BACKHOE ARM. BECAUSE SPACE VITAL ON A MOON PROJECT, THIS VERSATILITY PERMITS ONE TRACTOR TO BE USED FOR SEVERAL DIFFERENT FUNCTIONS.

THE LUBRICATION / COOLANT SYSTEM BEGINS WITH THE TEFLON BEADS BEING PUMPED BY A PROGRESSING CAVITY PUMP DOWN THE CENTER OF THE SHAFT. ONCE AT THE BOTTOM, THE BEADS PASS THROUGH THE DIAMOND DRILL BIT AND PICK UP THE SHAVINGS CREATED. THIS MIXTURE CONTINUES UPWARD WHERE IT ENTERS A CENTRIFUGAL FILTER AFTER REACHING THE SURFACE. CENTRIFUGAL FORCES MOVE

97.	DA	R. 100	DISC
Deorge	INVEN	Burdell	ON T
2	Juni	19	<u> 5</u>

HIS 2 DAY OF JUNE 18 85

LOSED TO AND UNDERSTOOD BY ME DISCLOSED TO AND UNDERSTOOD BY ME ON THIS & DAY OF MUNI 19 1 auous

THE LIGHTER BEADS OUTWARD WHERE THEY PASS ON THROUGH THE SYSTEM WHILE THE HEAVIER DIRT PARTICLES DROP TO A TANK. AFTER THE FILTER, THE BEADS RETURN TO THE PUMP WHERE THE PROCESS CONTINUES.

THE MOST ORIGINAL IDEA IMPLEMENTED INTO THIS CORE DRILL IS THE USE OF TEFLON BEADS. TEFLON, DEVELOPED BY DUPONT, IS JUST BEGINNING TO BE USED IN THE BEAD FORM. ALTHOUGH EXPENSIVE TO PRODUCE, THE BEADS WITHSTAND THE HIGH TEMPERATURES AND OFFER CONSTANT VISCOSITY FOR THE SYSTEM.

ON THIS 2 DAY OF JUNE 19 85

DISCLOSED TO AND UNDERSTOOD BY ME DISCLOSED TO AND UNDERSTOOD BY ME

## REFERENCES

- 1. Kanol P. E., Engineering Properties of Coils: NY, Prontice Mail (1975)
- 2. Das M. B., Introduction to Soil Mechanics: The Town State University (1979)
- S. American Society For Testing Materials, Vane Sheer and Cone Penetration Resistance Testing of In Situ Soils.
- 4. Ruiter J. de., Current Perstrometer Practice (1900) Asce 284-81
- 5. ASAS Oultural Practices Equipment Committee. Coil Cons Penetrometer (recomfirmed 1589). ASAS 8313.1-73
- 6. European Symposium on Penetration Testine Vol. 2 General Reports, Discussions, and Other Potivities, 1977
- 7. Normis G. M., Come Penetration Testing and Experience, Published by RSCE (1981)

# ME 4182 LECTURE SERIES 2:00 - 3:00 SKILES 168

PRODUCT LIABILITY Jenniffer Fletcher January 28

Griffin, Cochrane & Marshall

MATERIALS FOR SPACE APPLICATIONS Feburary 4

Roy Mead

Lockheed-Georgia Company

ETHICS IN ENGINEERING DESIGN February 11

Dr. Kezios Georgia Tech

"ENGINEERS: TURNING IDEAS INTO REALITY" National Engineers Week Speaker February 18

U.S. PATENT SYSTEM February 25

Todd Deveau

Newton, Hopkins & ormsby

HUMAN FACTORS; THE MAN-MACHINE INTERFACE March 4

Veterans Administration Medical Center

(TO BE ANNOUNCED) March 11